

PETERS DRAIN 2021

Township of Adelaide Metcalfe

ADDENDUM NO. 1

Our Job No. 219293

**PLEASE INDICATE RECEIPT OF THIS ADDENDUM BY
SIGNING BELOW AND EMAILING BACK TO:**

aneely@adelaidemetcalfe.on.ca

Spriet Associates robk@spriet.on.ca

ALSO, A COPY OF THIS ADDENDUM IS TO BE ATTACHED TO THE TENDER WITH SUBMITTAL

I hereby acknowledge receipt of Addendum No. 1

NAME (Please Print)

Company

1. Branch 2 – The Catchbasin note on the extent of work should read as follows:
“Supply and install one 600mm x 600mm ditch inlet catchbasin including berms with Turfmat overflow chutes, grates, leads, removal and disposal of existing catchbasins”
2. Branch 2 – the 185m of 250mm sewer pipe on the extent of work should read concrete tile, as shown on the drawing.
3. Branch 2 – The note at sta. 0+650 on the profile drawing should say:
“Locate and connect any existing tile to new 200mm Conc. tile”

SPRIET ASSOCIATES LONDON LIMITED



Rob Keidel, Civil Engineering Technologist.